

QC Metallurgical, Inc.

Testing & Consulting Services

2870 Stirling Road • Hollywood, FL 33020-1199 • (954) 889-0089 • Fax (954) 362-5742

INSPECTION REPORT

Revised 08/05/2020

DATE May 20, 2020

QCM JOB# 20EM-293 CUSTOMER Stone Hardscapes

DESCRIPTION 1 sample Xtreme Grip Marble

CUSTOMER ORDER# Verbal MATERIAL _____

INSPECTION SPECIFIED Dynamic Coefficient of Friction

APPLICABLE SPECIFICATIONS ANSI A137.1

RESULTS OF INSPECTION

COEFFICIENT OF FRICTION ANALYSIS RESULTS

	Average	Min.	Max.
Dry 1	0.82	0.66	0.88
Dry 2	0.81	0.71	0.90
Dry 3	0.82	0.65	0.90
Dry 4	0.79	0.65	0.87
Result:	0.81		

Wet 1	0.82	0.74	0.87
Wet 2	0.80	0.71	0.87
Wet 3	0.82	0.68	0.92
Wet 4	0.79	0.71	0.87
Result:	0.81		

Spec: .42 minimum

Sample is acceptable per ANSI A137.1.


Jerry Iacofano